

NO.	THE ROOM	P(m2)	O(m)	floor	the wall	the ceiling
1	corridor - warm connection	10.94	13.47	PVC	grease plinth 1.5m / semi-dispersion	Armstrong
2	toilet for patients	1.80	5.80	ceramic ceramic	ceramic. tiles 2m / semi-dispersion	Armstrong
3	staff toilet	1.80	5.80	tiles. tiles	ceram. tiles 2m / semi-dispersion	Armstrong
4	doctor's room	11.59	13.68	PVC	semi-dispersion	Armstrong
5	corridor - waiting room	28.60	26.75	PVC	fat plinth 1.5m /semi- dispersion	Armstrong
6	patient preparation	15.49	16.30	PVC	semi-dispersion	Armstrong
7	magnet technical room 10:00 a.m.		14.00	cast epoxy	semi-dispersion	semi-dispersion
8	magnetic resonance imaging (MRI) inside the lining of the FC	35.00	24.00	antistatic PVC	faraday cage panel lining	Armstrong
9	MRI control room 12:50 p.m		15.00	PVC	semi-dispersion	Armstrong
10	technical room - electrical	5.10	9.10	cast epoxy	semi-dispersion cast epoxy	semi-dispersion
11	technical room - water	2.60	6.60	semi-dispersion	semi-dispersion facade	paint facade paint
	12 canopies	20.70		concrete		

